



NEW SURVEY
OF EXISTING PARCEL
RICHLAND COUNTY
TAX MAP OFFICE

EAJ 2-11-09
INITIAL DATE



BURKHOLDER, AARON, Survey
Pt. of NE Qtr. of Sec 34, Twp 23, R. 18
Bloominggrove Twp.,
Richland Co., State of Ohio

Robert M. Little
Robert M. Little
Reg. Prof. Surv. # OH 5524
January 1, 2009

AA-123

Robert M. Little

Surveyor and Engineer

67 Redwood Rd., Mansfield, OH 44907

Phone and Fax 419-756-5056

Aaron Burkholder
Shiloh, OH 44813

Being part of the NorthEast Qtr. Of Sec. 34, Township 23, Range 16, in Bloominggrove Township, County of Richland, State of Ohio, and being further described as follows:

Commencing at a P.K. nail, found, marking the intersection of centerlines of Mansfield-Norwalk Road, S.R. 13, and Shiloh-Newville Road, S.R. 603,

Thence South $00^{\circ}26'19''$ East a distance of 483.13' to a P.K. nail found, said course being with the centerline of said S.R. 13;

Thence South $88^{\circ}08'36''$ West distance of 246.63' to an iron pin, set and capped, said point being the POINT OF BEGINNING, passing two iron pins, found, at 30.13' and 193.89', at said bearing;

thence South $88^{\circ}08'36''$ West, a distance of 26.55' to an iron pin, set and capped;

thence South $02^{\circ}17'13''$ East, a distance of 511.08' to an iron pin, found;

thence North $87^{\circ}57'58''$ East, a distance of 26.25' to an iron pin, found;

thence North $02^{\circ}15'11''$ West, a distance of 511.00' to the POINT OF BEGINNING;


said described tract containing 0.31 Acres, more or less, but subject to all highways and easements of record.

Bearing Basis: Survey Drawing I-449.

Grantees, their heirs and assigns do hereby covenant and agree that the parcel of land described in this instrument or any portion thereof does not constitute a principal building site under applicable zoning and will not be conveyed by said grantees, heirs and assigns, independent and separate from any adjoining or continuous parcel fronting on a public highway or street.



Robert M. Little
Reg. Prof. Surv. # 5524
Jan. 1, 2009



NEW SURVEY
OF EXISTING PARCEL
RICHLAND COUNTY
TAX MAP OFFICE
EAK 2-11-09
INITIAL DATE

AA-123