X-27

X-27

PLAT FOR
LAMP WORKS
PUMPING STATION
being pt. of in-LOT
1343 SHELBY OHIO
SCALE 1" = 30'

1911

TUCKER AVE.

50'

CENTER OF PROPOSED IMPROVEMENT

BLACKFORK CREEK

MARY E. SMITH

1343

ELEV. 125.2
GRADE 123.16

⊕61 ELEV. 131.2

30'

GRADE 7/0 .226

STAKE LINE

67.57'

THIS GROUND ABOUT
2' HIGHER THAN STA 61.
ELEV. 133.0

EDGE OF BANK

BANK ELEV.
ABOUT 138.00

N
W E
S

60+20.42

37.36'

15'

10'

18'

19.42'

ELE. 125.8
GRADE 123.88

STA 60+01

60

44.66'

ELE 129.1

163' TO STAKE LINE
195.36' TO CENT. OF PROPOSED IMPROVEMENT

12'

1294

1295

1296

1297

1298

50'

50'

50'

50'

160'

PARK AVE.

1311

1312

1313

1314

1315

50'

50'

SIMEON AVE.

30'

32.36

30'

APPROXIMATE ELEV. OF FLOOD 135.5
B.M. X ON S.W. CORNER OF E. ABUTMENT
OF TUCKER AVE BRIDGE
ELEV. 137.27.

Shelby-Ohio.

46